DESIGN DEVELOPMENT
SUBMISSION CHECKLIST - FOOD

Equals 70% of Final Design Submission Pack

- ❑ Design Response
    - ❑ Provide a coordinated developed-design package that reflects the approved Concept Design and addresses all applicable RDM and consultant review comments.
    - ❑ Include a response register cross-referencing each previous design review comment to the relevant drawing or schedule.
- ❑ Developed Floor Plan - 1:50
    - ❑ Show the lease line, building grid lines, shopfront and entry, closure line, partitions and doors, customer and staff circulation, dining and service zones, joinery, fixtures, furniture, equipment and back-of-house areas.
    - ❑ Dimension the tenancy layout, shopfront set-out, circulation widths, storage areas and locations of fixtures and equipment.
    - ❑ Show dry, chilled and frozen storage, food preparation, wash-up and waste areas, with sufficient capacity for the proposed operation.
    - ❑ Show access, maintenance and operational clearances, including access to services cupboards and equipment.
    - ❑ Show ordering, payment and collection points, and the storage and presentation of condiments, cutlery, napkins, trays and other customer-facing items where applicable.
- ❑ Floor Finishes Plan - 1:50
    - ❑ Identify floor finishes, finish codes, transitions, thresholds, movement joints, finished floor levels, gradients and ramps.
    - ❑ Show the slab and finished floor levels nominated on the Landlord's Tenancy Drawings and demonstrate a flush junction with the common mall floor finish.
    - ❑ Show floor wastes, waterproofing extents, coving and other hygiene-related floor details within kitchens, food preparation, wash-up and waste areas.
    - ❑ Where floor build-ups are proposed, provide the build-up methodology, depth, extent and loading information for structural review.
    - ❑ Show how base-building movement joints are accommodated and integrated with the proposed floor finishes and waterproofing.
- ❑ Shopfront and Internal Elevations - 1:20 / 1:50
    - ❑ Provide each public-facing shopfront elevation at 1:20, showing the lease line, shopfront form, entry and closure, glazing, signage, counters, food display, menus, principal materials, levels and key dimensions.

- ❑ Provide internal elevations at 1:50 showing wall finishes, joinery, fixtures, equipment, food displays, signage, lighting and integrated services.

- ❑ Clearly identify finish codes and cross-reference all relevant schedules and detail drawings.

- ❑ Sections and Detail Drawings

  - ❑ Provide sufficient sections through the shopfront, entry, floor and ceiling interfaces, counters, food displays, kitchens, joinery and other key design features.

  - ❑ Provide the mall tile-to-tenancy floor threshold junction detail, nominating slab level, mall finished floor level, tenancy floor finish and complete floor build-up.

  - ❑ Provide the shopfront-to-mall ceiling interface detail, incorporating a 10-15mm shadowline between the shopfront and mall bulkhead or ceiling.

  - ❑ Provide fire hose reel cupboard and inter-tenancy wall/shopfront junction details. Refer to the applicable Uptown project typical details.

  - ❑ Detail the treatment of movement joints through floors, walls, ceilings and columns, including waterproof treatment where required.

THRESHOLD AND SHOPFRONT DETAILING - DESIGN CONSIDERATIONS
The available setdown at the mall tile-to-tenancy floor junction may be as little as 15mm. Select and detail the proposed floor finish and build-up to suit the available setdown.
Maximise glazing panel sizes and detail adjoining panes with a minimal air gap and no visible silicone. The shopfront structural engineer is to consider these requirements when developing the glazing design and specification.

- ❑ Joinery and Equipment Drawings - 1:20

  - ❑ Provide plans, elevations, sections and details for all custom joinery, counters and food displays, including dimensions, materials, finishes, hardware, fixing and installation methods.

  - ❑ Show integrated storage, equipment, services, ventilation and access requirements.

  - ❑ Provide structural engineering for heavy, suspended or otherwise non-standard joinery, equipment and fixing systems where required.

- ❑ Reflected Ceiling Plan - 1:50

  - ❑ Show ceiling heights and finishes, lighting, signage, access panels, speakers, security devices and all other visible services.

  - ❑ Coordinate the RCP with the approved Services Drawings Submission and cross-reference lighting, signage and equipment schedules.

  - ❑ Show the location and architectural integration of exhaust hoods, diffusers, grilles, speakers, security cameras and associated power and data connections.

CEILING, SECURITY AND SOUND - DESIGN CONSIDERATIONS
Visible services, including speakers and security cameras, are to be coordinated and finished to integrate with the ceiling design.
Where a sound system is proposed, locate speakers a minimum 3000mm from the entry, do not fix them to inter-tenancy walls, and provide a sound leveller set to a maximum 75dB. Speakers are to sit flush with the ceiling.

- ❑ Lighting Design Package
    - ❑ Provide a colour-rendered lighting plan, lux-level calculations and technical data sheets for all proposed light sources.
    - ❑ Show the intended lighting hierarchy, colour temperature, colour rendering, beam angles, dimming and control requirements.
    - ❑ Show shopfront zone lighting and signage circuited to a 24/7 timer and set to the hours directed by Centre Management.
- ❑ Signage, Menus and Graphics Package
    - ❑ Provide signage and menu elevations and details showing location, dimensions, materials, finishes, illumination, fixing methods and concealed power supplies.
    - ❑ Provide the developed graphics and branding package, including artwork intent, locations, dimensions, colours, materials and application method.
    - ❑ Cross-reference all signage, menus and graphics to the relevant architectural drawings and schedules.
- ❑ Schedules
    - ❑ Provide coordinated schedules for materials and finishes, lighting, equipment, fittings and fixtures, furniture, signage and menus.
    - ❑ For each item, identify the supplier, manufacturer, product or model number, description, finish, intended location and a reference image.
    - ❑ Include installation or fixing details, order lead time and current stock availability where known.
- ❑ Updated Coloured 3D Visualisations
    - ❑ Provide updated coloured 3D visualisations that accurately reflect the Design Development drawings, materials, finishes, lighting, signage and menus.

VISUALISATION REQUIREMENTS
Visualisations must accurately correspond with the submitted plans, elevations, dimensions, materials and architectural form. Solely AI-generated visualisations are not accepted as architectural design submissions.
Where AI-assisted content is used, identify it as an AI-assisted visualisation in a footnote to each affected image.

- ❑ Physical Materials Sample Board
    - ❑ Submit an in-hand physical sample board of the key architectural materials and finishes, in addition to the Materials and Finishes Schedule.

- ❑ Label each sample with its finish code, supplier and product reference, and cross-reference it to the submitted drawings and schedule.
- ❑ Provide one complete physical sample board to Vicinity to retain on file.

❑ Authority and Consultant Documentation

- ❑ Identify the appointed Building Certifier, Council Health Officer or food-premises consultant, commercial kitchen designer and other relevant consultants, and include applicable design guidance or approval conditions.
- ❑ Include structural engineering for the shopfront, glazing, signage, overhead elements, joinery, equipment, fixings, floor build-ups and other elements where required.
- ❑ Demonstrate that food-premises finishes, layouts and fixtures have been developed to meet applicable health and food-safety requirements.

❑ Design Submission

- ❑ Present the Design Development Submission at a face-to-face meeting with your Vicinity RDM.
- ❑ Submit all drawings, schedules and consultant documentation listed in this checklist as one combined PDF set for review, rather than as multiple individual PDF files.
- ❑ Provide clear drawing titles, drawing numbers, scales, revision numbers and revision dates throughout the submission.
- ❑ Cloud all changes from the previous issue and cross-reference them to the applicable revision number.