Annexure 16

GAS REQUIREMENTS

Gas Meter Installation to Food Tenancies CHADSTONE

Action by an Landlord (Vicinity)

Action by Tenant/Shopfitter

Action by Head Contractor

Step 1

Application for Gas from Street to Gas Meter Enclosure to the Authority (Multinet)

Application submitted and is processed by the Authority (Multinet)

if yes

Step 2

Install pipework from Gas Meter Enclosure to Tenancy.

Note Tenancy gas shut off valve is located under the slab.

Installation of tenancy gas pipework to start from tenancy gas shut off value into tenancy. Shopfitter to install their own shut off value within the tenancy.

Step 3

Meter Fix Application submitted to Retailer (Origin) for all Tenancies/Kiosks requiring gas meters (TBC.)*

* Has a 8no. week lead time for installation of gas meters

This will complete the gas from the street via meter to the tenancy

Once meter has been signed off by Retailer

Step 4

Landlord to transfer account name to Tenant

Step 5

Tenant to accept account in their name prior to gas becoming live