

ALUMINOUS OUTDOOR LIGHTING PRODUCT CATALOG

CUSTOM DECORATIVE BASE POLES

SERIES PORT MARIA SPECIFICATIONS - PTMDB

Aluminous
114 Healey Road
Bolton, ON L7E 5R2


aluminous.com

ALUMINOUS
LIGHTING SYSTEMS

INTRODUCTION

This catalogue has been designed to assist you in selecting an area lighting product, which will meet your specific requirements. The diverse selection of pole sizes and mounting bracket options offered within this catalogue i.e. architectural, roadway traffic and tapered elliptical brackets, should accommodate most of your lighting needs. However, if the scope of your specifications or requirements cannot be fulfilled with these standard products, please contact us: we can custom-design an array of products to meet any criteria or specification.

WIND SPEED MAP



The wind speed map shows the maximum steady wind expected within a 50-year period of recurrence at an elevation of 30 feet above ground. If standards are mounted above grade, please call for assistance if needs arise. Since winds are unpredictable and usually involve gusts EPA calculation allows for a 1.3 gust factor. Aluminous Outdoor Lighting Products have been designed to withstand a specific wind load for each lighting standard. Please note: selecting the proper size pole for a specific application requires one to know the EPA of the total number of fixtures. Because of the different wind velocities in any geographical area reference should be made to the area where the pole is being installed. Proper selection should be made from the Canadian and U.S. Wind Speed Map. Aluminous Outdoor Lighting Products EPA rating is in conformity with the requirements of the AASHTO Standard specifications for structural support for poles and arm brackets. Please note: All maximum wind speeds are measured in mph (miles per hour).

CONTACT INFORMATION

Address: 600 Ferguson Avenue North Hamilton, Ontario L8L 4Z9 | **Telephone:** 1-877-625-7240 905-526-1771 |

Fax: 1-888-700-8656 905-526-6161 | **Email:** sales@aluminous.com | **Website:** www.aluminous.com

CUSTOM DECORATIVE BASE POLES

STRAIGHT SHAFT

Catalogue Number	Nominal Height	Weight (approx.)	Anchor Bolt Size
PTMDB-S-8	8'	90 lbs	3/4" X 24"
PTMDB-S-10	10'	94 lbs	3/4" X 24"
PTMDB-S-12	12'	105 lbs	3/4" X 24"
PTMDB-S-15	14'	120 lbs	3/4" X 24"

FLUTED SHAFT

Catalogue Number	Nominal Height	Weight (approx.)	Anchor Bolt Size
PA-FL-8	8'	95 lbs	3/4" X 24"
PA-FL-10	10'	99 lbs	3/4" X 24"
PA-FL-12	12'	110 lbs	3/4" X 24"
PA-FL-14	14'	125 lbs	3/4" X 24"



NOTES:

LUMINAIRE	Manufactured by others. Please ask for details.
FINISH	Powder coat finish available in standard or custom colour.
MATERIAL	6063 Aluminum alloy heat treated to produce a T6 temper.
ANCHOR BOLT PROJECTION	3-4 inches
BCD	Size TBD

Welding Conforms to CSA W47.1 and W47.2

Need Help? Talk to Jerry: 905 857 8100

CUSTOM DECORATIVE BASE POLES - PTMDB



NOTE: DECORATIVE POLE DRAWING IS FOR ILLUSTRATIVE PURPOSE ONLY. PLEASE CONTACT OUR OFFICE FOR DETAILED SHOP DRAWING AS PER YOUR REQUIREMENT.

ALUMINOUS LIGHTING SYSTEMS Roadway. Commercial. Institutions. 114 HEALEY RD., BOLTON, ONTARIO L7E 5R2 PHONE: 905-857-8100 FAX: 905-857-8131	DRAWN BY NANDISH	DATE 2019-08-21
	DESCRIPTION: PORT MARIA - DECORATIVE POLE ALUMINOUS STOCK	
	MATL: ALUMINUM	
<small>THIS DOCUMENT IS THE PROPERTY OF ALUMINOUS LIGHTING PRODUCT AND IS LOANED SUBJECT TO RETURN ON DEMAND. UNDER NO CIRCUMSTANCES IT IS TO BE REPRODUCED OR COPIED IN WHOLE OR IN PART. THE CONTENTS ARE CONFIDENTIAL AND MUST NOT BE SUBMITTED TO OUTSIDE PARTIES FOR USE OR EXAMINATION. ALL PRODUCTION AND INTELLECTUAL RIGHTS RESERVED.</small>	CATALOGUE NO: PORT MARIA	<u>REV</u> 0