


ALIAS|AFFIRMA PRIMA LX RIO



ABOVE GROUND POOL OVAL INSTALLATION MANUAL

V35020
(AFRAME)

06.2020

ABOVE GROUND POOL SAFETY

PLEASE READ BEFORE INSTALLATION



WARNING

FAILURE TO HEED THESE WARNINGS CAN RESULT IN PERMANENT INJURY, PARALYSIS FROM A BROKEN NECK, ELECTROCUTION OR DROWNING. THIS POOL IS NOT DESIGNED FOR DIVING OR JUMPING! DANGEROUS INJURY CAN RESULT. SHALLOW WATER!

Carefully read, understand and follow all information in this user manual before installing and using the swimming pool. These warnings, instructions and safety guidelines address some common risks of water recreation, but they cannot cover all risks and dangers in all cases. Always use caution, common sense and good judgment when enjoying any water activity. RETAIN THIS INFORMATION FOR FUTURE USE.

Your pool contains a large quantity of water, and is deep enough to present inherent dangers to life and health unless the following safety rules are strictly observed. First-time users run the highest risk of injury. Make sure everyone understands and encourage all users especially children to learn how to swim. Learn Basic Life Support (Cardiopulmonary Resuscitation-CPR) and refresh this knowledge regularly. Instruct all pool users, including children, what to do in case of an emergency. Keep a working phone and a list of emergency phone numbers near the pool. This can make a life-saving difference in the event of an emergency. To ensure your pool is used safely you **MUST** observe the following safety precautions:

1. NO JUMPING OR DIVING

The top rail of your pool is not a walkway and must not be used for jumping or diving. Do not permit jumping or diving into the pool from a deck or the top rail of the pool. Diving or jumping into the pool can result in serious injury.

2. NEVER USE THE POOL ALONE

Never permit the pool to be used unless it is attended by at least one person other than the bather. Someone should always be available to lend assistance in an emergency. Designate a competent adult to supervise the pool each time it is being used. Vigilant supervision of weak swimmers and non-swimmers by a competent adult is required at all times, remembering that children under five are at the highest risk of drowning.

3. NEVER LEAVE CHILDREN UNATTENDED

Never leave a child alone and unsupervised in or near the pool—not even for a second. There is no substitute for constant adult supervision.

4. NO ROUGH PLAY

Do not permit "roughhousing" in and around your pool. Surfaces can become slippery and hazardous when wet.

5. LIGHT THE POOL AT NIGHT

If the pool is used after dusk, adequate lighting must be provided. Illumination in the pool area must be sufficient to clearly judge pool depth and all features in and around the pool. For lighting recommendations, consult your local licensed electrical contractor.

6. RESTRICT ACCESS TO THE POOL

Do not leave chairs or other furniture beside the pool that could be used by a child to climb up into the pool. Ladders must be removed whenever the pool is unattended. A fence with a lockable gate around the pool or yard is strongly recommended and may be required by law in some jurisdictions. Secure doors and windows, where applicable to prevent unauthorized access to the swimming pool. Remove all toys from the swimming pool and surrounding area when not in use to avoid attracting children to the pool. Barriers, pool covers, pool alarms or similar safety devices are helpful aids, but they are not substitutes for continuous adult supervision.

7. NO ALCOHOL OR DRUGS

Never drink alcoholic beverages, use any intoxicants or medication which could hinder your judgment and reflexes.

8. KEEP YOUR POOL CLEAN AND SANITARY

Your filter system will remove suspended particles from the water and the surface skimmer will remove insects, leaves and other debris from the water surface. Use the correct pool chemicals as directed to destroy harmful bacteria and prevent formation of algae. Remember, unsanitary water is a serious health hazard.

9. KEEP OFF TOP LEDGES

Do not walk on top ledges. They can be slippery and they are not a walkway.

10. POOL COVER SAFETY

The cover must have a tamperproof locking retainer cable that positions the cover around the pool wall and keeps it securely in place. Never allow anyone, especially small children on the cover. Asphyxiation or drowning could result. Be sure to remove pool cover completely from the water surface before entering the pool. When purchasing any pool cover, please consult a swimming pool professional.

11. ELECTRICAL HAZARD

Never touch or attempt to service electrical equipment, including the filter when your body and/or the ground is wet. Electrocution or permanent injury due to high voltage (120V AC) could result. The pool should be bonded in accordance with Section 680-26 of the National Electrical Code. For further assistance contact your dealer or a local licensed electrician. Do not use pool during electrical or rain storms.

12. SAFETY EQUIPMENT

Keep a safety rope 1/4" by 50" with a flotation buoy with an outside diameter of 15". Have accessible in a prominent area by your pool. Keep a pole not less than 16 feet (4.88m) long with a blunt or hook end available at poolside in case of emergencies. Weak swimmers and non-swimmers should wear personal protection equipment when using the pool.

13. POOL CHEMICALS

Store pool chemicals out of the reach of children. Do not place chlorine, chlorine tablets or sticks directly into skimmer, or winterize your pool with liquid chlorine. Damage to the skimmer, pool liner and filter will result. Failure to obey this instruction will void all component warranties. Always follow chemical manufacturer's instructions when storing, handling and dispensing pool chemicals.

14. CHECK FOR DAMAGE

Periodically check your pool and ladder components for damage and wear. Be sure all screws are in place. Replace all damaged or worn components and tighten all screws before you use the pool, deck or ladders. At first sign, remove rust and touch up immediately.

15. POOL PARTS

Never modify the pool or accessories, or remove or drill holes in the pool, deck or ladder components unless instructed. Your pool wall is made of thin metal, there is an inherent cut hazard with metal so use gloves during installation. Always use Original Equipment Manufactured parts for your replacement parts.

FOLLOW ALL SAFETY INSTRUCTIONS

Read and follow all safety instructions packaged with pool, ladder, deck or any other accessory. Additional pool safety publications can be obtained by contacting: The Association of Pool & Spa Professionals (www.apsp.org)



IMPORTANT NOTICE READ BEFORE INSTALLATION!

The safety stickers must be installed as per following instructions. Failure to properly install warning labels will void warranty. Failure to mount these safety labels may subject you to substantial liability in case of injury. These warnings are not to be removed under any circumstances! If they become discolored or fall off please request replacements which will be sent at no charge.

PLACE SIGN ON LINER ABOVE WATER LINE, OPPOSITE ENTRY TO POOL



PLACE SIGN ON WALL NEXT TO POOL ENTRY



REMEMBER TO WATCH CHILDREN



IMPORTANT INFORMATION ABOUT YOUR LINER

We do not make or supply liners for our pools.

Please contact your liner's manufacturer with questions or if instructions are not included with the liner.

Liner must be installed per the liner manufacturer's instructions.


Incorrect liner installation may void the warranty.

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

PARTS LISTING

Alias
PALI-52SSSSSSA10
Round



IMPORTANT NOTE:


Make sure you have all the parts necessary before you start installation.

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

PARTS LISTING

Alias STR
PALI-AF52SSSSSSA10
A-Frame
Oval



Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

PARTS LISTING

Product Description: Product Code :			Alias Oval PALI-AF52SSSSSA10						Revised Sept 2019
			Quantity required for installation (by pool size)						
Index #	Description	Part #	1022	1219	1224	1525	1530	1833	
A	Top ledge 42" (round section)	SDT768-1278042	10						
A	Top ledge 50" (round section)	SDT768-1278050		10	10				
A	Top ledge 52" (round section)	SDT768-1278052				12	12	14	
A	Top ledge (straight section)	SDT768-1278030	8	4	8	6	10	10	
B	Upright (round section)	SDT768-R12619	8	8	8	10	10	12	
B	Upright (straight section)	SDT768-O12619	10	6	10	8	12	12	
C	Ledge cover	SD768-27100ABC	18	14	18	18	22	24	
C 1	Ledge cover Plug	SD768-27100C	18	14	18	18	22	24	
E	Top plate	20666	26	22	26	28	32	36	
F	Stabilizer 30" (straight section)	LA1254130	8	4	8	6	10	10	
F	Stabilizer/bottom rail(round section)	LA1254110	12						
F	Stabilizer 10' SP (trans.section)	LA1254110X	8						
F	Stabilizer/bottom rail(round section)	LA1254112		12	12				
F	Stabilizer 12' SP (trans.section)	LA1254112X		8	8				
F	Stabilizer/bottom rail(round section)	LA1254115				24	24		
F	Stabilizer/bottom rail(round section)	LA1254118						28	
G	Steel bars	11823	2	2	2	2	2	2	
H	Wall		1	1	1	1	1	1	
I	Screw 12x3/4" Stainless	V12X34	184	147	184	184	225	247	
J	Angle base plate	SDT768-2071432	8	4	8	6	10	10	
K	End channel	20611	10	6	10	8	12	12	
L	Lateral support	SDP768-R20693	10	6	10	8	12	12	
M	Reinforcement part	20555-57	10	6	10	8	12	12	
N	U connector	21123	10	6	10	8	12	12	
O	Bottom plate	20671	10	6	10	8	12	12	
P	Hook	20690	10	6	10	8	12	12	
Q	Brace plate	20719	4	4	4	4	4	4	
R	Steel strap 23"	2054923		3	5				
R	Steel strap 40"	2054940						6	
R	Steel strap 59"	2054959	10	6	10	12	18	18	
S	Truss phill 18-8 bolts 18-8 1/4-0x3/4	99-0023	31	31	31	31	31	31	
T	Flange nuts S/S 1/4-20 Serrated	2FGS422	31	31	31	31	31	31	
*	Hardware bag for pool	SACV12X34-184	1		1	1			
*	Hardware bag for pool	SACV12X34-147		1					
*	Hardware bag for pool	SACV12X34-225					1		
*	Hardware bag for pool	SACV12X34-247						1	
**	Hardware bag for wall	1050000054	1	1	1	1	1	1	
***	Hardware bag for A frame	SACAJF1224	1		1				
***	Hardware bag for A frame	SACAJF1219		1					
***	Hardware bag for A frame	SACAJF1525				1			
***	Hardware bag for A frame	SACAJF1530					1		
***	Hardware bag for A frame	SACAJF1833						1	
	Bolt 18-8 1/4"-20 X1"	2TPS100	155	99	155	126	181	193	
	Bolt 1/4"-20 X 3"	B14X20X3	11	7	11	9	13	13	
	Nut 1/4"-20	N14X20	166	106	166	135	194	206	
	Instruction DVD	SACWBI36876	1	1	1	1	1	1	

* In the hardware bag for pool you will find parts: #V12X34

** In the hardware bag for wall you will find parts: #99-0023 - #2FGS422


*** In the hardware bag for A frame you will find parts: #2TPS100 - #B14X20X3 - #B14X20X78 - #N14X20

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

PARTS LISTING

Affirma
PALI-52SSSSSSA10
Round



IMPORTANT NOTE:


Make sure you have all the parts necessary before you start installation.

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

PARTS LISTING

Affirma STR
PALI-AF52SSSSSSA10
A-Frame
Oval



Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

PARTS LISTING

Product Description:			Affirma Oval						Revised Sept 2019
Product Code :			PALI-AF52SSSSSA10						
			Quantity required for installation (by pool size)						
Index #	Description	Part #	1022	1219	1224	1525	1530	1833	
A	Top ledge 42" (round sections)	SDT768-1278042	10						
A	Top ledge 50" (round sections)	SDT768-1278050		10	10				
A	Top ledge 52" (round sections)	SDT768-1278052				12	12	14	
A	Top ledge (straight sections)	SDT768-1278030	8	4	8	6	10	10	
B	Upright (round sections)	SDT768-R12619	8	8	8	10	10	12	
B	Upright (straight sections)	SDT768-O12619	10	6	10	8	12	12	
C	Ledge cover	SD768-27100ABC	18	14	18	18	22	24	
C 1	Ledge cover Plug	SD768-27100C	18	14	18	18	22	24	
E	Top plate	20666	26	22	26	28	32	36	
F	Stabilizer (straight sections)	LA1254130	8	4	8	6	10	10	
F	Stabilizer/Bottom Rail (Round sections)	LA1254110	12						
F	Stabilizer 10' SP(trans.sections)	LA1254110X	8						
F	Stabilizer/Bottom Rail (round sections)	LA1254112		12	12				
F	Stabilizer 12' SP (trans.sections)	LA1254112X		8	8				
F	Stabilizer/Bottom rail (round sections)	LA1254115				24	24		
F	Stabilizer/bottom rail (Round sections)	LA1254118							28
G	Steel bars	11823	2	2	2	2	2	2	
H	Wall		1	1	1	1	1	1	
I	Screw 12x3/4" Stainless	V12X34	184	147	184	184	225	247	
J	Angle base plate	SDT768-2071432	8	4	8	6	10	10	
K	End channel	20611	10	6	10	8	12	12	
L	Lateral support	SDP768-R20693	10	6	10	8	12	12	
M	Reinforcement part	20555-57	10	6	10	8	12	12	
N	U connector	21123	10	6	10	8	12	12	
O	Bottom plate	20671	10	6	10	8	12	12	
P	Hook	20690	10	6	10	8	12	12	
Q	Brace plate	20719	4	4	4	4	4	4	
R	Steel strap 23"	2054923		3	5				
R	Steel strap 40"	2054940							6
R	Steel strap 59"	2054959	10	6	10	12	18	18	
*	Hardware bag for pool	SACV12X34-184	1		1	1			
*	Hardware bag for pool	SACV12X34-147		1					
*	Hardware bag for pool	SACV12X34-225					1		
*	Hardware bag for pool	SACV12X34-247							1
**	Hardware bag for wall	1050000054	1	1	1	1	1	1	
***	Hardware bag for A frame	SACAJF1224	1		1				
***	Hardware bag for A frame	SACAJF1219		1					
***	Hardware bag for A frame	SACAJF1525				1			
***	Hardware bag for A frame	SACAJF1530					1		
***	Hardware bag for A frame	SACAJF1833							1
	Truss phill 18-8 bolts 18-8 1/4-0x3/4	99-0023	31	31	31	31	31	31	
	Flange nuts S/S 1/4-20 Serrated	2FGS422	31	31	31	31	31	31	
	Bolt 18-8 1/4"-20 X1"	2TPS100	155	99	155	126	181	193	
	Bolt 1/4"-20 X 3"	B14X20X3	11	7	11	9	13	13	
	Nut 1/4"-20	N14X20	166	106	166	135	194	206	
	Instruction DVD	SACWBI36876	1	1	1	1	1	1	

* In the hardware bag for pool you will find parts: #V12X34

** In the hardware bag for wall you will find parts: #99-0023 - #2FGS422


*** In the hardware bag for A frame you will find parts: #2TPS100 - #B14X20X3 - #B14X20X78 - #N14X20

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

PARTS LISTING

Prima DLX
PPRILX-52SSSSSSA20
Round



IMPORTANT NOTE:


Make sure you have all the parts necessary before you start installation.

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

PARTS LISTING

Prima DLX
PPRILX-AF52SSSSSSA20
A-Frame
Oval



Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

PARTS LISTING

Product Description : Product Code :			Prima DLX PPRILX-AF52SSSSSSA20			Revised Sept 2019
			Quantity required for installation (by pool size)			
Index#	Description	Part #	1218	1224	1530	
A	Top ledge 32" (round sections)	GRT726-1278032	4	4	4	
A	Top ledge 35" (round sections)	GRT726-1278035	2	6	8	
A	Top ledge 38" (round sections)	GRT726-1278038	10	10		
A	Top ledge 49" (round sections)	GRT726-1278049			10	
A	Top ledge (straight sections)	GRT726-1278030				
B	Upright (round sections)	GRT726-R12619	12	12	12	
B	Upright (straight sections)	GRT726-O12619	4	8	10	
C	Ledge cover	GR726-27100ABC	16	20	22	
D	Top plate	20666	28	32	34	
D	Bottom plate	20671	4	8	10	
E	Wall channel Omega Galv 30" (straight	LA1253530	2	6	8	
E	Wall channel Omega Galv 32" (straight	LA1253212	8	8		
E	Wall channel Omega Galv 49" (straight	LA1254915			20	
E	Wall channel Omega 12' (round	LA1253812	20	20		
E	Wall channel Omega 15' (round	LA1253215			8	
F	Steel bars	11823	2	2	2	
G	Wall		1	1	1	
H	Screw 12 X 3/4"	V12X34	168	205	225	
I	Angle base plate 32"	GRT209-2071437	2	6	8	
J	End channel	20611	4	8	10	
K	Lateral support	GRP708-R20693	4	8	10	
L	Reinforcement part	20555-57	4	8	10	
M	U connector	21123	4	8	10	
N	Hook	20690	4	8	10	
O	Brace plate	20719-37	2	4	4	
P	Steel strap 23"	2054923	2	4		
P	Steel strap 59"	2054959	4	8	15	
Q	Bolt 1/4"-20 X1"	2TPS100		126	155	
R	Bolt 1/4"-20 X 3"	B14X20X3	5	9	11	
S	Nut 1/4"-20	N14X20	64	135	166	
T	Bolt 1/4"-20 X 7/8"	B14X20X78	59			
*	Hardware bag/pool	SACV12X34-204		1		
*	Hardware bag/pool	SACV12X34-225			1	
**	Hardware bag/wall	1050000054	1	1	1	
***	Hardware Kit A-Frame	SACAJF1525		1		
***	Hardware Kit A-Frame	SACAJF1224			1	
***	Hardware Kit A-Frame	SAC729P1218	1			
	Truss phill 18-8 bolts 18-8 1/4-0x3/4	99-0023	31	31	31	
	Flange nuts S/S 1/4-20 Serrated	2FGS422	31	31	31	
	Instruction DVD	SACWBI36876	1	1	1	

* In the hardware bag/pool you will find part: V12X34

** In the hardware bag/wall you will find parts: #99-0023 - 2FGS422


*** In the hardware bag/pool you will find parts: #2TPS100 - #B14x20x3 - #N14x20 - #B14x20x78 - #V12x34

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

PARTS LISTING

Rio STR
PRIO-52SSSSSSA20
Round



IMPORTANT NOTE:


Make sure you have all the parts necessary before you start installation.

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

PARTS LISTING

Rio STR
PRIO-AF52SSSSSSA20
A-Frame
Oval



Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

PARTS LISTING

Product Description :			Rio Oval				Revised Sept 2019
Product Code :			PRIO-AF52SSSSSSA20				
			Quantity required for installation (by pool size)				
Index#	Description	Part #	1022	1224	1525	1530	
A	Top ledge 42" (round sections)	GRT726-1278042	10				
A	Top ledge 50" (round sections)	GRT726-1278050		10			
A	Top ledge 52" (round sections)	GRT726-1278052			12	12	
A	Top ledge (straight sections)	GRT726-1278030	8	8	6	10	
B	Upright (round sections)	GRT726-R12619	8	8	10	10	
B	Upright (straight sections)	GRT726-O12619	10	10	8	12	
C	Top plate	20666	26	26	28	32	
C	Bottom plate (straight section	20671	10	10	8	12	
D	Stabilizer/Bottom Rail (straight sections)	LA1254130	8	8	6	10	
D	Stabilizer/Bottom Rail (round sections)	LA1254110	12				
D	Stabilizer/Bottom Rail (round sections)	LA1254110X	8				
D	Stabilizer/Bottom Rai; (round sections)	LA1254112		12			
D	Stabilizer/Bottom Rail(round sections)	LA1254112X		8			
D	Stabilizer/Bottom Rail(round sections)	LA1254115			24	24	
E	Ledge cover	GR726-27100ABC	18	18	18	22	
F	Steel bars	11823	2	2	2	2	
G	Wall		1	1	1	1	
H	Screw 12x3/4	V12x34	184	184	184	225	
I	Angle base plate 32"	GRT48-2071432	8	8	6	10	
J	End channel	20611	10	10	8	12	
K	Lateral support	GRP708-R20693	10	10	8	12	
L	Reinforcement part	20555-57	10	10	8	12	
M	U connector	21123	10	10	8	12	
N	Hook	20690	10	10	8	12	
O	Steel strap 23"	2054923		5			
O	Steel strap 59"	2054959	10	10	12	18	
P	Brace plate	20719	4	4	4	4	
Q	Bolt 18-8 SS 1/4"-20 X1"	2TPS100	155	155	126	181	
R	Bolt 1/4"-20 X 3"	B14X20X3	11	11	9	13	
S	Nut 1/4"-20	N14X20	166	166	135	194	
*	Hardware bag for pool	SACV12X34-184	1	1	1		
*	Hardware bag for pool	SACV12X34-225				1	
**	Hardware bag/wall	1050000054	1	1	1	1	
***	Hardware bag / A-Frame	SACAJF1224	1	1			
***	Hardware bag / A-Frame	SACAJF1525			1		
***	Hardware bag / A-Frame	SACAJF1530				1	
	Truss phill 18-8 bolts 18-8 1/4-0x3/4	99-0023	31	31	31	31	
	Flange nuts S/S 1/4-20 Serrated	2FGS422	31	31	31	31	
	Instruction DVD	SACWBI36876	1	1	1	1	

* In the harwdare bag/pool you will find parts: #V12x34

** In the hardware bag/wall you will find parts: #99-0023 - #2FGS422

*** In the hardware bag/A-Frame you will find parts: #B14x20x78 - #B14x20x3 - #N14x20 - #2TPS100

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

READ ALL INSTRUCTIONS CAREFULLY


The approximate time it takes for installation, excluding earthworks and filling is about 1 day.
You will need at least 3 people to help with installation.

A. DETERMINE THE LOCATION OF YOUR POOL

1. The Terrain

Pay special attention to choosing the right location for your pool:

- Choose a large area, as flat and level as possible and well drained. **(Image 1)**
- Choose a spot on dry, firm earth (stabilizer or other)—do not install the pool on asphalt, tar or oil based surfaces, gravel, peat moss, wood or chemically treated soil.
- Check with your pool dealer to see if Nut Grass grows in your area. This type of grass may grow up through your pool liner. Your dealer will be able to advise how best to treat the site.
- Sloped areas will need to be made level by digging away high spots, not by filling low spots—be prepared to hire earth-moving equipment if necessary.
- Ensure the earth is well compacted and a wall is placed to prevent the earth from seeping out. **(Image 2)**
- If you need to install partly in the ground, you must contact your dealer to see if this is an option for you and that you meet law requirements in your jurisdiction. **(Image 3)**



Important Note:

Ground preparation is one of the most important steps in the installation process. A proper foundation will ensure the rest of the pool assembly goes smoothly and that no problems will occur when the pool is filled with water.

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

A. CONT. DETERMINE THE LOCATION OF YOUR POOL




2. Things to Avoid

Do not locate your pool near or on any of the following **(Images 4 to 6)**:

- Overhanging tree branches.
- Overhead wires and clotheslines.
- Buried pipes and wires. Contact your gas, electric and telephone utilities to find buried pipes and wires before you dig.
- Areas with poor drainage.
- Grass, stones and roots. Grass will rot underneath the pool liner, and stones and roots will damage the pool liner.
- Areas recently treated with oil-based weed killers, chemicals or fertilizers.

3. Plan Ahead

- Will you be adding an adjacent deck later? Be sure to leave room.
- Will you be using pool accessories or other appliances that need electricity or gas? Locate your pool near these services or plan to have them installed later by a licensed contractor.



Important Note:


When locating the centre of the pool, be sure to take into consideration any structures (deck, patio, house) or relevant items (change rooms, gazebo, etc.) that the pool may need to line up with and ensure that the pool is in the most visual pleasing location for your property.

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

A. CONT. DETERMINE THE LOCATION OF YOUR POOL

4. Tools Needed



Compactor



Hammer



Water hose



Level



File



Vacuum cleaner



Pliers



Rake



Lawn roller



Metal snips



Screwdriver



Wheelbarrow



Shovel



Spraypaint



Mallet



Measuring tape



Duct tape



Trowel



Wrench



 Gloves

List of required materials

- Straight wood plank
- Material that provides a permanent base (ex. Crushed stone)
- Fine sand (void of debris)
- Cement blocks (5cm x 20cm x 40cm / 2"x 8"x16") (optional)
- 2x Plywood (60cm x 120cm / 2ft x 4ft)
- Wood board (30cm x 20cm / 1ft x 1ft)
- Vinyl covered hooks (to hold wall steady)
- String and stakes & wooden pegs
- Prefabricated cove sections (optional)
- Pool carpeting (optional)
- Rope
- Polyethylene Plastic Sheeting

- Optical Level
Can be useful for precise measurements



Important Note:

Wall edges, skimmer and water return holes may be sharp, it is important to wear gloves when installing.

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

B. PREPARE THE FOUNDATION OF YOUR POOL


1. Mark out the area

- a. The next following steps will show you how to mark out the area you need for the oval pool. This marked area will be larger than the pool size itself, but this space is needed. Find a site where the ground is stable, level and well drained. Once you have selected your site, determine where the middle of your pool will be.

See Diagrams:

Please see in the next page for an **EXAMPLE** on how to correctly mark your pool area.
Please verify your pool's **FOOTPRINT** for correct measurements on the last pages of this Section 1.

- b. Drive a peg into the ground at the centre point.
(Image 1)
- c. Now you must make the round ends that will be the oval part. In order to do so, you will have to determine the center of the radius on each side and drive a peg into the ground. **(Image 2)**
- d. Using a length of string tied between the peg and a can of spray paint mark the circles on the ground. **(Image 3)**
- e. Once the center has been established, and the measurement of the pool itself has been determined, you must now determine the outer limits of the perimeter of your pool. Add 12" (30cm) outside this measurement to determine pool perimeter. **(Image 4)**



Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION




B. CONT. PREPARE THE FOUNDATION OF YOUR POOL

- f. Mark areas along both straight sides of your oval. Use pegs and string as a guide for the can of spray paint to mark straight lines. **(Image 5)**
- g. You now have the space marked out that is needed for your oval pool. **(Image 6)**

2. Remove the sod

- a. Remove the sod from the area you have just outlined. **(Image 7)**
- b. Remove all debris (rocks, roots, etc) using a rake. Then compact the ground to achieve a firm base.

You can use a sod removal machine.



Important Note:

Your pool must be perfectly level. Take the time you need to be sure your foundation is perfectly level.


Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

B. CONT. PREPARE THE FOUNDATION OF YOUR POOL

Example on how to mark out pool area for an 18 x 33

Please be sure to use your pool's footprint for your pool size on the last pages of this Section1.



Perimetre 1043"(hole to hole)-Track length measured in track slot-All dimensions are in inches

EXAMPLE



Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

B. CONT. PREPARE THE FOUNDATION OF YOUR POOL


3. Make the area flat and level

- Remove all the high spots with a shovel, hoe or rake. To make sure your pool is stable, compact the ground well before adding the sand. Be prepared to hire earth moving equipment if you need to level a large area. Remember, your pool must be level across the diameter of the pool. **(Image 8)**
- Small dips and hollows may be filled in, but the soil must be hard-packed with a tamping tool or a soil compactor machine.
- Take material such as rock dust or fine mortar that can conform a solid, permanent base and deposit this material around the rim of the basin. **(Image 9)**
- The material used should be spread around the perimeter of the pool to a width of 24" (60cm) and a thickness of 2" (5cm). **(Image 10)**
- Recheck the outer perimeter of the oval shape, where the pool wall will be placed. Compact the ground and make sure there are no high or low spots. The bottom edge of the pool wall must rest flat on the ground and have no gaps under it.



Helpful Hint:
Use the optical level to ensure that the ground is perfectly flat and level.

Important Note:
Your pool must be perfectly level. Take the time you need to be sure your foundation is perfectly level.





Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

C. PRE-ASSEMBLY OF THE BRACED SECTION (A-FRAME)

1. Assembling the braced section

- Attach the hook to the end of the end channel with a mechanical screw and nut. **(Image 11)**
- Attach the joiner plate (the one with slots to receive the "U" connector together with two (2) mechanical screw and nuts on the end channel. **(Image 12)**
- Attach the reinforcement part (vertical bar) to the joiner plate with a mechanical screw and nut. **(Image 13)**






Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

C. CONT. PRE-ASSEMBLY OF THE BRACED SECTION (A-FRAME)

- d. Attach the uprights to the outside of the recessed parts of the joiner plate using two (2) screws. **(Image 14)**
NOTE: The uprights (with the two(2) holes in the center) should not be confused with the uprights that are used.
- e. Slide the lateral support into the hook. The end of the lateral support with the sharpest angle must be fastened to the bottom hook and not to the upright. **(Image 15)**
- f. Attach the lateral support to the upright and reinforcement part as well as the end channel, using mechanical screws and nuts. **(Images 16 & 17)**

Repeat the installation of the lateral supports.




Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

C. CONT. PRE-ASSEMBLY OF THE BRACED SECTION (A-FRAME)


- g. Assemble the angled base plates of the two sides of the straight section of the pool, using two (2) mechanical screws and nuts, in the TOP TWO HOLES ONLY. **(Image 18)**



- h. Insert the pre-assembled angled base plates in the row of the uprights. **(Image 19)**

- i. Secure the angled base plates to the end channels using mechanical screws and nuts. **(Image 20)**

18



19



20

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION



C. CONT. PRE-ASSEMBLY OF THE BRACED SECTION (A-FRAME)

- j. Position a steel strap so that the holes line up with those on the brace plate. Attach the strap to the plate (in the first four holes) using mechanical screws and nuts as illustrated. The head of the screws must be on top of the brace plate and not on the bottom. **(Image 21)**

Note: The ends of the base plates with the holes farthest apart should be turned towards the uprights. To make the task easier, use a screwdriver to align the holes.

- k. Install the brace plate so that the last two holes line up with the last two holes on the end channel and attach both parts using mechanical screws (head on top) and nuts. **(Image 22)**

Note: The four brace plates must always be installed at the extremities of the straight sections of the pool. Install the remaining steel straps.





Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

D. GROUND PREPARATION FOR THE LATERAL SUPPORTS

1. Digging the trenches

- a. Place nails in front of the lateral supports to mark their position. **(Image 23)**
- b. Back up the lateral supports to prepare the ground where they will be installed. **(Image 24)**




Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION


D. CONT. GROUND PREPARATION FOR THE LATERAL SUPPORTS

- c. Dig the areas where the end channels are to be installed. Dig to a depth of 4,5 cm (1 3/4"). Please to your pool's footprint at the end of this section 1 to find out the exact dimensions of your pool.
(Image 25)

If you have decided to install your pool on a cement floor, make sure to provide spaces in the cement where the end channels will be situated. This space can be provided for during the pouring of the cement by using wood planks 11 cm x 4 cm x 104 cm (4 3/8" x 1 3/4" x 41") according to your pool model.



- d. Join straps end to end with mechanical screws and nuts always using the two end holes of each strap to cover the full width of the pool in order to join with the opposite brace plate. Again place the head of the screws on top and not on the bottom. **(Image 26)**





Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

D. CONT. GROUND PREPARATION FOR THE LATERAL SUPPORTS

2. Install Patio Stones (Blocks)

- a. Dig, install and level a patio block or equivalent approximately 8"x 16"x2" (20x40x5cm) in size, under the end of each lateral support. The patio block must be placed as indicated in image 27, this will help to ease and spread water pressure.
(Images 27 & 28)



Section 1


GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

D. CONT. GROUND PREPARATION FOR THE LATERAL SUPPORTS

- b. Measure the two intersecting axes to ensure that the two straight sections are parallel. **(Image 29)**

Note:

It may feel tedious to be always measuring, but this only helps to ensure proper installation and avoiding problems further on.



29


3. Proceed to Section 2 - Assembling the Pool Base

**THE FOLLOWING SECTION
CONTAINS YOUR POOL'S FOOTPRINT**

Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION


OVAL FOOTPRINT - 10 x 22



Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION


oval footprint - 12 x 19



Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION


OVAL FOOTPRINT - 12 x 24



Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

oval footprint - 15 x 25




Section 1

GENERAL INSTRUCTIONS - OVAL POOLS

GROUND PREPARATION


OVAL FOOTPRINT - 15 x 30



Section 1

GENERAL INSTRUCTIONS - OVAL POOLS GROUND PREPARATION

OVAL FOOTPRINT - 18 x 33



Section 2

GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL BASE

A. INSTALLATION OF BOTTOM PLATES AND BOTTOM RAILS


1. Bottom rails - straight section

- a. If your pool size is one of the following; 10'x22', 12'x19' or 12'x24', you must insert a transition rail into bottom plate at the end of each straight section on either side. **(Images 1 & 2)**

NOTE: Pool sizes mentioned above will come with two types of rails and stabilizers. Transition rails/stabilizers have less curve compared to the other rails/stabilizers.

If your pool size is one of the following; 15'x25', 15'x30' or 18'x33', insert a bottom rail into the bottom plate at the end of each straight section.

NOTE: There are no bottom rails used in the bottom of the straight section.



Section 2

GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL BASE



A.CONT. INSTALLATION OF BOTTOM PLATES AND BOTTOM RAILS

2. Bottom plates - round section

- a. Continue the installation of the bottom plates of the round sections. Insert the end of each bottom rail into the bottom plate. Leave a gap between the ends of the bottom rails. **(Images 3 & 4)**

Voir les diagrammes:

Veuillez consulter l'empreinte de votre piscine pour mesure l'espace nécessaire,



Section 2


GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL BASE

A. CONT. INSTALLATION OF BOTTOM PLATES AND BOTTOM RAILS

3. Patio Stones (Optional) For Round Section

- Concrete patio stones may be placed at the base of each upright of your pool. **(Image 5)**
- Each bottom plate will show the location for a patio stone. Make a mark in the ground at each base plate.
- Remove the bottom rails and bottom plates and lay out the patio stones around the circle where the bottom plates were.
- The patio stones must be sunk into the ground so the tops are flush with the soil around them. **Use the carpenter's level to make sure the patio stones are perfectly level and flush with the ground.** Use either the carpenter's level and a 2-by-4 (5cm x 10cm) wood plank, or the optical level between patio stones to make sure the stones are level with each other. **(Image 6)**
- Do not install blocks or rails on loose sifted soil or sand. There must be no space between the ground and the bottom of the rails. All patio blocks must be flush with the ground, solid and level with each other in all directions.

NOTE: Installing patio blocks is optional and the blocks may shift due to temperature changes.



Important Note:

Make sure the patio stones are perfectly level and flush with the ground. All patio blocks must be flush with the ground, solid and level with each other in all directions.

Section 2

GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL BASE

A. CONT. INSTALLATION OF BOTTOM PLATES AND BOTTOM RAILS

4. Measure the perimeter of your pool

- Measure the perimeter of your pool and hammer nails into the ground to keep the bottom rails into place. These nails are to be removed only at the last step-when filling up the pool.
- Verify the height of each bottom plate with an optical level. Ensure that they are the same height.


Important Note:

Use a soft measuring tape to measure around the perimeter of the pool. Measure from the inside of the bottom rail, the measurement should equal the wall length.


5. Fill inside the pool area

- Fill sand under the pressure plates first, make sure it is well compacted.
- Pour sifted sand in the centre of your pool. Ensure that you will have enough to spread approximately 2" (2.5cm) around the inside pool area. **(Image 7)**
- Spread the sand inside the pool area. Make sure not to spread the sand onto or beyond the bottom rails. Compact the sand manually or mechanically. **(Image 8)**

6. Proceed to Section 3 - Assembling the Pool Wall



7



8

Section 3

GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL WALL

A. SETTING UP THE POOL WALL

Do not attempt to install the pool wall in the wind, wait for a calm day.
It takes at least 3 people to install the pool wall.


1. Preparing for the wall installation

- Bring the following items into the middle of the pool foundation before you start uncoiling the pool wall: plywood, some extra sand or fine dirt to make the cove and a ladder to climb out after the wall is assembled.
- Make sure the skimmer and water return holes are located where you need them to be. The skimmer and water return holes are positioned towards the end of the wall, **(the section before where the wall started)**.



Important Note:

Wall edges, skimmer and water return holes may be sharp, it is important to wear gloves when installing.



2. Set the pool wall in place.

- Unpackage the coiled pool wall and stand it on 2 pieces of plywood at the place close to where you need to install the skimmer. **(Image 1)**
(Remember the skimmer and water return holes will be placed at the section just before where you started the wall installation).
- Start uncoiling the wall, guiding the bottom edge into the curved bottom rail. The starting end of the wall must be positioned in the centre of a bottom plate, and the skimmer and return holes should be positioned where the pump and filter will be. **(Image 2)**
- As you erect the wall, install the stabilizers temporarily to obtain greater stability. You should also use heavy vinyl-covered hooks and rope to hold the wall steady. Ideally, however, you should work with several people. **(Image 3)**
- When uncoiling the wall, the skimmer and return holes are positioned toward the end of the wall.



Important Note:

It is preferable to use very fine sand that is easily compacted. Be careful not to spill sand on the bottom rails. Be sure to clear sand or stone dust from the bottom rails otherwise the wall will buckle.


Section 3

GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL WALL


A. CONT. SETTING UP THE POOL WALL

3. Join the ends of the pool wall


- Line up the holes in the two ends of the pool wall.
(Image 4)
 - Now that you have installed the wall you can be faced with three scenarios.
 - The wall joints align perfectly, if so, move on to the next step (c).
 - Your wall appears to be too short. **It is not.** However the space between the bottom rails must be decreased by lightly tapping the bottom plates towards the inside of the pool. You can also tap the wall lightly with both hands in the desired direction. **(Image 5)**
 - Your wall appears too long. **It is not.** However the space between the bottom rails must be increased by tapping the bottom plates lightly towards the outside of the pool or by tapping the wall with both hands in the desired direction. **(Image 6)**
- You **MUST** recheck the gaps at each and every one of the bottom rails so that they are all equal in gap size.
- 3) Your wall appears too long. **It is not.** However the space between the bottom rails must be increased by tapping the bottom plates lightly towards the outside of the pool or by tapping the wall with both hands in the desired direction. **(Image 6)**
- You **MUST** recheck the gaps at each and every one of the bottom rails so that they are all equal in gap size.



4



5



6



Important Note:

Bottom rails must always be held in place in the bottom plate.



Important Note:

You **MUST** recheck the gaps at each and every one of the bottom rails so that they are all equal in gap size.

- Recheck the position of the upright, refer to your pool's footprint diagram.

Section 3

GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL WALL


A. CONT. SETTING UP THE POOL WALL

- d. To fasten the wall joint, overlap the two steel bars, one on the inside and the other on the outside. Tighten the mechanical screws on the inside and the nuts on the outside. Ensure that all bolts and all the holes are used.
(Image 7)




Important Note:

Stick a screwdriver through two of the holes to help line up the ends of the wall.



When tightening the screws start from either the top and go down or vice versa. Do not start a few screws from top and a few from the bottom to meet in the middle, this can cause problems later on.

- e. Adjusting the pool to the proper shape may cause the bottom rails and bottom plates to slip out of alignment a little. Recheck all of the bottom plates to make sure each one is centred where the bottom rails meet.
- f. Cover the seam and bolt heads on the inside/interior of the pool wall completely with 2" (50mm) duct tape.
(Image 8)



Important Note:

The pool must be level across the perimeter. A pool that is not level is dangerous and may collapse.

Section 3

GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL WALL



B. ASSEMBLING THE COVE

1. Make the cove

- If you are using sand, bank the sand against the wall to form a cove of 3" to 6" (7.5cm to 15cm) high and 8" to 12" (20cm to 30cm) wide at ground level. This will prevent the liner from creeping under the wall, and it will also protect the liner from any metal edges of the pool framework. **THIS STEP IS NOT OPTIONAL, IT MUST BE DONE. (Image 9)**

NOTE: If a smaller cove (less than 3" (7.5cm)) is made along with using a very tight liner, this will buckle the wall.

- Water the sand to compact it and use a trowel to spread it evenly. **IMPORTANT: You must ensure that the sand is very well compacted. (Image 10)**
- Since earth containing chemicals can cause discoloration or corrosion, it is suggested that you place **polyethylene plastic sheeting** under the cove around the perimeter of the wall, so no earth comes in contact with the metal. Since the presence of such chemicals is beyond the control of the manufacturer, such damage is not covered under warranty. **(Image 11)**
- If you are using styrofoam cove pieces instead of sand, insert them in the bottom rail and refer to the installation instructions that are provided with them.
- Proceed to your liner instructions and after liner installation proceed to Section 4-Installing the pool frame.



Important Note:

The cove is an important part of the pool structure. Take your time to make a complete, full-size cove.



IMPORTANT INFORMATION ABOUT YOUR LINER

We do not make or supply liners for our pools.

Please contact your liner's manufacturer with questions or if instructions are not included with the liner.

Liner must be installed per the liner manufacturer's instructions.

Incorrect liner installation may void the warranty.

Section 4

GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL FRAME

A. INSTALLATION OF THE UPRIGHTS

1. Install the uprights - ROUND SECTION

- a. The wall joint is hidden behind the upright on most pools. This assures that the skimmer and skimmer return holes are not obstructed.
- b. Insert an upright into the bottom plate. Ensure that the upright is correctly inserted into the bottom plate. **(Image 1)**
- c. Please note that the holes meant to receive the ledge cover are placed asymmetrically. This means that the holes which are at each extremity of the upright are not placed at the same distance from each extremity of the upright.
- d. Using two (2) screws (V12x34) attach the bottom of the uprights to the bottom plates. **(Image 2)**

Proceed with the installation of the uprights



Important Note:

Use a level to make sure the upright column is straight up and down.



Important Note:

Ensure to leave a gap between the two bottom rails.

See Diagram:

Please refer to your pool's footprint (Section 1) for gap measurement.



Section 4

GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL FRAME

B. INSTALLATION OF THE STABILIZERS AND TOP PLATES

1. Install stabilizers and top plates

- Install the stabilizer on the wall while ensuring to leave a gap between each end. Insert the stabilizer into either side of the top plate. **(Image 3)**
- Position stabilizers and top plates just assembled on top of wall by slightly tapping them with a mallet. Make sure the recessed portion of the top plates lie to the inside of the uprights.
- Ensure that the upright is level.
- Attach the upright to the top plate using screws (V12x34). **(Image 4)**

Repeat until you have installed all the stabilizers and top plates.




Important Note:

Ensure to leave a gap between the two stabilizers.

See Diagram:

Please refer to your pool's footprint (Section 1, last page) for gap measurement.



Section 4

GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL FRAME

C. INSTALLATION OF TOP LEDGE AND LEDGE COVERS

1. Install top ledge and ledge covers

- a. Place top ledges on the wall. Align the holes on the top ledges with those on the top plates. Make sure the space left between each top ledge is uniform all around and that the space in question can be covered by a ledge cover. Attach the top ledges to the top plates using screws (V12x34). **(Images 5 & 6)**
- b. Place inside ledge cover onto the joiner plate and attach ledge cover with a screw (V12x34). **(Image 7)**

Note-: During assembly, the inner and outer components of the ledge cover may have been slipped into each other for packaging purposes.



Important Note:

We suggest that you install all the top ledges on the wall before attaching them.




Section 4

GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL FRAME

C. CONT. INSTALLATION OF TOP LEDGE AND LEDGE COVERS

- c. Slide the exterior ledge cover into the interior ledge cover guide. NOTE: The plug is often located inside the ledge cover. Make sure you remove it before installing the ledge cover. **(Image 8)**
- d. Attach the exterior ledge cover to the upright using a screw (V12x34). Install the finishing plug on the ledge cover. **(Images 9 & 10)**



⚠ Important Note:
We suggest that you install all the top ledges on the wall before attaching them.




Section 4

GENERAL INSTRUCTIONS - OVAL POOLS ASSEMBLING THE POOL FRAME

D. FILL YOUR POOL WITH WATER

1. Finish filling the pool

- Fill the pool with water to 2" (5cm) below the lowest opening. Make sure you remove any creases from the liner in the bottom of the pool before the water level gets too high.
- While the pool is filling, remove the nails that were holding the bottom rails in place.
- Your pool is now installed. You must now install the filter and pump, the skimmer and water return inlet. Please follow the installation instructions that come with these products.



Important Note:

Before making any openings in the liner, fill the pool with 60cm (24") of water to stretch the liner fully. When filling your pool, begin with a garden hose until there is about 30cm (12") of water in the pool. This will allow the liner to stretch gradually. You can then use a heavier flow to finish filling it up.

IMPORTANT:

Make sure that your pool is round, do not assume that by filling up the pool that this will help the pool to place itself into a perfect round circle. Ensure that it is round before filling up the pool with water.

IMPORTANT SAFETY INFORMATION:

Please refer to the safety page at the beginning of this instruction manual. You must follow the rules and information regarding placement of safety stickers on your pool.


**Section
4**

**GENERAL INSTRUCTIONS - OVAL POOLS
ASSEMBLING THE POOL FRAME**

E. BASIC FLOW OF SYSTEM

1. How the system flow should look like

- a. When assembled your pool should have a basic flow system as in this image, **PLEASE CONTACT YOUR DEALER** for more specific instructions.



Section 5

POOL MAINTENANCE

POOL MAINTENANCE

Keep your pool wall and frame clean. Always wash away any deposits of pool chemicals which land on the frame of your pool. Wash periodically with a mild soap solution (no abrasives). At least once a year use a clear non-yellowing household wax on all metal components.

Your pool and liner must be inspected regularly for leaks, corrosion, scratches, and punctures. If any problem is found **IMMEDIATE CORRECTIVE ACTION MUST BE TAKEN**. Small repairs and punctures in your liner may be easily repaired using repair kits available at your local dealer. Scratches on your pool wall & frame must be touched up with anti-rust enamel. Wire brush all rust and add a coat of enamel primer followed by a coat of color matching paint. Pool water is full of various caustic chemicals, which will corrode metal parts. If any corrosion is allowed to continue, failure of the pool structure may occur which could result in excessive property damage as well as bodily harm.

The skimmer & return area and below it are particular areas that must be carefully and regularly inspected. If this area is wet, and remains wet for any length of time, it usually means there is a small leak. Skimmer/skimmer return gaskets must be replaced when they become defective. Water must not be permitted to continually run down the wall, if neglected pool will break. If proper skimmer/skimmer return gasket care is not maintained, your warranty will be void!



Important Note:

Be sure to follow all local and state safety regulations when installing any accessory to your pool. Any decks, and all entries, must be carefully monitored for safety and access to pool. Installing any other manufacturer's deck or slide is strictly forbidden!

WINTERIZING YOUR POOL

Along with the cool nights of autumn comes the end of the swimming season. During the winter your pool is subject to more stress than in the summer, and any breakage that is caused by incorrect winter procedures is not subject to any warranty with this company.

All of our pools are designed to be left up all winter, but nonetheless are subject to the warranty that was purchased. Continue to chlorinate and filter until the pool is closed down. If you follow our recommendations, you will be able to winterize your pool properly in a few hours.


Properly winterizing your pool will protect it from damage and make it easier for you to reopen it when spring arrives.

The key to fast and easy winterization lies in regular treatment of the water until the start of the cold season, even if you haven't been using the pool.

Routine maintenance becomes easier and less frequent as the water gets cooler. In order to keep the water clean and clear and to prevent the liner from staining, we recommend closing your pool as late as possible, i.e. toward the end of September when the water temperature is about 10°C (50°F).

Waiting until you have finished closing the pool before shutting off the filtration system will prevent hoses still connected from freezing.

Follow the instructions on the following pages or contact your retailer for further information to ensure that you are protecting your pool properly.



CLOSING YOUR ABOVE GROUND POOL FOR THE WINTER

At the end of the season, you must follow these directions to make your pool ready for the winter. For areas where water freezes make sure to follow these instructions before the water is frozen, otherwise do not touch the frozen water, this may damage the pool.

STEP 1) PRIOR TO CLOSING

- a. Several days prior to closing your pool, test the water for the ph level, total alkalinity, and chloring. The water balance is important to protect the pool from corrosion or scale build-up during winter shut down.

STEP 2) PERFORM A COMPLETE INSPECTION

FINDING LEAKS

- a. Towards the end of the summer season or around mid-August, check for leaks by verifying if the pool's water level is stable. Draw a line on the liner marking the water level and wait 10 days. If after 10 days the level has dropped, then there is a leak. It is important to seal off any leaks you find. Leaks left unsealed when freezing begins can seriously damage your pool and even cause it to collapse.
- b. Vacuum carefully to remove all leaves and debris.

CHECK THE LINER

- a. Make sure the top of the liner is still attached to the pool wall. make sure there are no leaks. Repair any liner holes with a vinyl patch: any small punctures in the liner can be easily repaired with underwater repair kits available at your local retailer. Do not remove the liner from the pool, as removal of the liner will void the existing warranty.

CHECK ALL JOINTS AND SCREWS

- a. Make sure all the frame joints are fitting together properly and make sure the pool wall has not shifted from the bottom rail. Ensure all screws and bolts are tight.

CHECK FOR RUST

- a. Periodically inspect the metal parts for any corrosion especially around the skimmer area. If corrosion is found, immediate corrective action must be taken. Wire brush any rust and add a coat of enamel primer followed by a coat of color matching anti-rust enamel paint. Pool structure failure could result in major property damage and bodily harm. Paint any scratches with anti-rust paint.

CLOSING YOUR ABOVE GROUND POOL FOR THE WINTER CONTINUED

STEP 3) ADD CLOSING CHEMICALS

- a. To maintain water quality, use a winter kit which contains an algicide and chlorine especially designed for this purpose. When it's time for spring cleaning, this will save you hours of work and reduce the cost of chemicals needed to restore your water quality.
- b. If your pool has a bottom drain, you will have to use pool antifreeze to prevent it from freezing during the winter. Unscrew the hose from the base of the skimmer and attach an extension. Pass the extension over the wall of the pool, making sure it remains well attached. Pour antifreeze into the extension. Leave the valve open so that water can drain from the skimmer.

STEP 4) LOWER THE WATER LEVEL

- a. Lower the water level so as to leave between 6 to 20 inches (15cm to 50cm) below the water return. You may plug the return jet hole at this time. ****IMPORTANT**DO NOT PLUG THE SKIMMER DRAIN HOLE** (located at the base of the skimmer). Remove all hoses attached to the skimmer and return fittings. Do not let water freeze in the skimmer. Leave the skimmer attached to the pool wall and ensure that the skimmer lid is installed. **DO NOT DRAIN ALL THE WATER OUT OF THE POOL.**
- b. Depending on your area and if the freezing point is more aggressive, for example 50% is frozen into ice, we strongly suggest to lowering the water to lowest point. Depending on how great the deep freeze in your area **we suggest you consult with your local dealer about procedures on lowering the water level throughout the winter.** We also suggest throughout the autumn season to continually check this level before freezing season starts, as it must not reach the skimmer holes at any time during the winter. Remove any snow which may accumulate on the top ledge.

STEP 5) FILTER PREPARATION

- a. Disconnect the hoses from the filter. Remove and store the filter, ladder and all other removable parts from around the pool. The filter should be clear of any foreign objects and water should be removed from the filter and pump. See the manufacturer's instructions. Store the pump in a temperature controlled environment (so that it is not damaged by changes in temperature).

STEP 6) WINTER COVER

- a. For the winter cover we suggest to lower the water level to 1 inch (2.5cm) below the water return. In some areas your dealer may ask you to install it differently in order to protect the pool and the cover. Contact your local dealer to verify the correct procedure for your pool.
- b. If using a winter cover, make sure to place a ball underneath so that rainwater falls into the pool. An accumulation of too much water on the cover could place pressure on the pool, causing damage and invalidating the guarantee. Depending on how great the deep freeze in your area we suggest you consult with your local dealer about procedures on leaving the pool cover throughout the winter.

CLOSING YOUR ABOVE GROUND POOL FOR THE WINTER CONTINUED



IMPORTANT

Never let more than 30 cm (1') of snow accumulate on the pool wall; the wall is designed to support the lateral pressure of the pool water, not vertical pressure. With spring thaw, if water leaks from the skimmer or return outlet opening, place a tube at the opening so that the water will run off as far away from the basin of the pool as possible. PLEASE NOTE: Do not strike or hit a frozen pool. This would damage it. Do not disturb the pool till spring. If you have left the winter cover on the pool, make sure to remove accumulated snow after heavy snowfalls.



Important Note:

Whatever the type of valve or extension hose used, you must follow the technique described in this document to close your pool, otherwise your guarantee may be cancelled. Make sure to use antifreeze designed for pools.



Important Note:


An unsealed leak may comprise or cancel the guarantee on your pool.
Never leave water in any of the filtration system components due to the risk of damage during freezing.

PREPARING YOUR POOL IN THE SPRING

At the end of winter, allow the ice in the pool to thaw completely. When the temperature reaches approximately 10 °C (50 °F), you have to restart your filtration system, since algae and bacterial form more quickly as it gets warmer. Here is how to prepare your pool in a few simple easy steps.

- a. If your pool is equipped with a pool cover, remove the cover and cushion. Carefully remove with a hose any rainwater that has accumulated on the cover so it does not fall into your pool. Clean your cover and cushion and let them dry. Store them in a dry clean place.
- b. Attach the return inlet and skimmer to the filter. Bring the water level up to the middle of the skimmer. Get your filter working. Clean the bottom of the pool with the vacuum, taking care to place the filter in the “waste/drain” position. In this way you will eliminate particles of dirt without disturbing the sand in the filter, and will considerably reduce the need for “backwash rinsing” of the filter.
- c. Now that you have purified the water, you have to test it. It is very important that the pH level of your pool be between 7.6 and 7.8 and the pool’s alkaline content be between 80 ppm and 130 ppm. If you are unable to attain these levels, please contact your retailer who will gladly do these tests for you.



 **Important Note:**
Do not drain your pool to clean the water unless absolutely necessary (the water is recyclable). If you do empty your pool, don't leave it empty for too long or expose it to direct sunlight, as the liner may shrink.

PREPARING YOUR POOL IN THE SPRING CONTINUED

- d. When the pH and alkaline levels are ideal, apply a shock-treatment or chlorinate your water. Let it filter for 24 hours and again verify both the pH and free chlorine levels.
NOTE: Add chemical products to your pool after sunset, as sunlight rapidly destroys chlorine.
- e. Let it filter for several days until the water is clear and the pH and free chlorine levels have stabilized. Add a conditioner/stabilizer by carefully following the manufacturer's instructions. This will stop the chlorine from evaporating quickly in sunlight. Add the quantity of algicide required to prevent algae.
- f. You may now begin regular maintenance of your pool. Don't forget to obtain a new set of solutions for your water analysis kit every spring. The old solutions may give false results.
- g. Make sure that the skimmer (screws and adapter) is properly in place and tighten the water return fittings to prevent leakage and premature rusting of the pool wall or the lower part of the bottom rail.

HAVE FUN!

IF YOU FOLLOW THESE TIPS AND ASK YOUR DEALER FOR ANY OTHER ADVICE YOU MAY NEED, YOU WILL HAVE ALL THE INFORMATION NECESSARY TO GET YOUR POOL OPERATING AGAIN.

